

SECTION 01 74 19**CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL****1.1 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL**

- A. For projects where construction waste shall be generated, the Contractor shall develop and submit a “Construction Waste Management Plan” (CWMP) to the Dartmouth PM for their review and approval prior to the start of construction. The plan shall, at a minimum, identify the following items:
 - 1. Waste Identification: Indicate anticipated types and quantities of construction waste generated by the Work.
 - 2. Waste Reduction Work Plan: Indicate whether each material stream shall be salvaged, recycled, or disposed of in a landfill. Identify local receivers and processors of recycled materials, if applicable.
 - 3. Site Logistics Plan: Indicate number, size, and location of proposed dumpsters on site. Indicate the intended frequency and schedule for dumpster collection.
- B. For projects where site laydown area is limited, coordinate with Dartmouth PM on potential alternate locations for dumpsters across campus.
- C. Architect to verify whether there are any project-specific sustainability goals that may impact construction waste management and recycling goals. These goals should be included in the contract documents.

END OF SECTION 01 74 19