

SECTION 03450

PLANT-PRECAST CONCRETE

*PART 1 - GENERAL*

1. Dartmouth College must visit pre-cast plant prior to accepting the supplier and the product.
2. 5 recent references must be provided prior to the college and the architect considering the precaster.
3. The precast supplier must be in direct contract with the general contractor or construction manager. No sub/subcontractor relationships will be allowed for the manufacture and supply of the precast elements of the project.
4. No shipping of the product shall be allowed before 7 days cure time is realized for the product.

END OF SECTION